

MINSITRY OF INFRASTRUCTURE, COMMUNICATION, UTILITIES AND HOUSING

CONSULTANCY FOR BACKUP POWER SUPPLY TO THE NATIONAL EMERGENCY OPERATION CENTRE (NEOC)

ADDENDA NUMBER 2

Addenda Issue Date: Wednesday, 30th June, 2016

Bid Closing Date and Time: The bid closing date is Monday, 18th July, 2016 at 12:00 noon.

Purpose: The purpose of this Addendum is to make changes, additions, deletions, revisions and clarifications to the bid documents issued Wednesday, 8th June 2016 for the project referenced above. Bidders shall review the Addenda and requirements in detail and incorporate any effects the Addendum may have on their bid price.

Acknowledgement: Bidders must acknowledge receipt of any and all Addenda. All requirements of the bid documents remain unchanged except as cited herein.

1. AMENDMENTS:

The following data is provided for your information:

Readings

| | |
|-------------------|------------|
| Planning | 120.2 Amps |
| Lands and Surveys | 113.6 Amps |
| Radio Anguilla | 12.0 kW |
| DITES Server Room | 23.11kW |

After visiting the EOC building it was noted that it would not be possible to add the EOC to the Generator on its own without significant electrical work. The entire building would have to be connected based on the current electrical configuration.

The main distribution in the electrical room that we looked at during our site visit has two breakers. One breaker services all Air-conditioning via a panel on the roof. The total air conditioning load is 33.5kW. The second breaker feeds a panel downstairs in the storeroom which has separate breakers that feed the panels for the EOC and Police upstairs. The EOC was not occupied and as such no reading could be taken. However, it is estimated that there would be an additional 6kW to the A/C load.

The consultancy seeks to assist in coming to a decision as to whether the entire building should or can be connected to the generator or if the EOC wiring has to be separated.

Additional data is presented in the attached Spread sheets:

Secretariat Power Log Jan 2-3

Secretariat Log Pmax & Qmax Jan 2-3

DITES Server Room August 21 2015

End of Addenda No. 2